


### Opportunity for Regional Program

- Development of new regional water source
  - Deliveries for recharge of GW basins
- Significant favorable impact on future probabilities of regional supply shortages
- Increased diversity consistent with IRP
  - Conservation
  - Desalination
  - Recycling
  - Stabilization of imported water supplies
- Emergency storage benefits



### Metropolitan & LACSD

- Decade of discussions on water recycling
  - 2010-12 Pilot studies on treatability of effluent
  - 2015 Discussions on a potential partnership
- November 2015 Board authorized
  - Agreement with LA County Sanitation District No. 2 for development of potential regional recycled water program
  - Recycled water demonstration project
  - Feasibility and financing studies


#### **Demonstration Plant**

- Treatability of JWPCP effluent proven
  - Two years of successful pilot testing
  - Operational experience at other facilities
- Allows for optimization of full-scale plant
  - Nitrogen management
  - Need for Microfiltration
- Provides water quality data for regulators
- Allows for coordinating operations with LACSD
- Provides venue for public outreach




Performance	Operational Scenarios	
	Base Case	Alternative Operations
Goal	Delivery Flexibility	Maximize Deliveries
AWT Production Capacity	150	150
Average Daily Delivery	145-150 mgd	<150 mgd
Minimum Day Delivery	>=110 mgd	<150 mgd
Manage Peak Flows	No	No
Additional Infrastructure and Facilities Needed (not currently included in the Base Case)	No	Yes (spreading basins and injection wells)







#### **Full-Scale AWT Base Case Overview**

- Receive unchlorinated, non-nitrified secondary effluent from JWPCP
- Produce high-quality water suitable for groundwater recharge
  - 150 mgd product water design capacity
  - Meet current basin objectives
- Use tertiary MBR (tMBR) to achieve pathogen log reduction and minimize membrane fouling














## Orange County Groundwater Basin

- Adequate Demand for Project Water
  - Imported Demand = 160-250 TAFY
  - Current replenishment Demand = 65 TAFY
- Sufficient Well Capacity to Pump Water
  - Existing Capacity = 420-440 TAFY
- Limited by Available Spreading Capacity
  - Winter = 18 MGD
  - Summer = 60 MGD
  - Would need additional 30-60 Ac. spreading capacity (just to spread current replenishment demand)



#### **About Sanitation Districts**

- Wastewater and Solid Waste Management
  - Serves 5.3 million people
  - 800 sq. mile service area
  - 460 MGD current average flow
  - 11 water reclamation plants, including Joint Water Pollution Control Plant (JWPCP)
- JWPCP
  - Located in Carson
  - Current Flow ~ 265 MGD
  - Primary and secondary treatment
  - Currently discharges to the ocean

## Agreement Terms: Demonstration Plant

- Boards approved
- LACSD Responsibility:
  - Deliver secondary-treated water to demo plant
  - Provide land & utilities
  - Dispose of waste streams
  - Perform influent lab analyses & maintain source quality control program
- Metropolitan Responsibility:
  - Fund, design, construct, operate & maintain AWT demo plant

# Agreement Framework: Full Scale Facilities

- Boards approved
- LACSD Responsibility to:
  - Deliver secondary-treated source water to AWT plant
  - Commit to level of quality for source water
  - Implement, enforce (& strengthen if necessary) ongoing source quality control program
  - Dispose of brine & waste streams
  - Lease land for AWT plant

## Agreement Framework: Full Scale Facilities

- Boards approved
- Metropolitan responsibility:
  - Provide AWT plant & delivery system
    - Fund, design, construct, operate & maintain entire system
    - Determine phasing
  - Provide exchange water into LACSD service area
    - Approx. 1% of product water
- Sales Revenue
  - Metropolitan revenue

## **Additional Considerations**

- Potential cost sharing by LACSD
- Potential State Funding
  - Grant funds & SRF low interest loans
  - Joint funding application
  - Phasing of requests to match progress of program
- CEQA Compliance for Full Scale Phase 1
  - AWT plant
  - Delivery system