



MEDITERRANEAN LANDSCAPE

Shade Exposure



PLANT KEY

Symbol	Botanical Name / Common Name
	<i>Coprosma repens</i> 'Marble Queen' / Variegated Mirror Plant
	<i>Camellia sasanqua</i> 'Yuletide' / "Yuletide" Autumn Camellia
	<i>Clivia miniata</i> 'Aurea' / Yellow flowering Kaffir Lily
	<i>Dianella tasmanica</i> 'Variegata' / Variegated Flax Lily
	<i>Woodwardia fimbriata</i> / Giant Chain Fern
	<i>Chondropetalum Tectorum</i> / Small Cape Rush
	<i>Ceanothus griseus horizontalis</i> 'Yankee Point' / Ceanothus 'Yankee Point'
	<i>Salvia chiapensis</i> / Chiapas Sage
	<i>Raphiolepis indica</i> 'Ballerina' / Dwarf Indian Hawthorne
	<i>Erigeron karvinskianus</i> / Santa Barbara Daisy
	<i>Campanula portenschlagiana</i> / Dalmation Bellflower
	Mulch



***All projects must include a minimum of 3 plants per 100 square feet of turf removed.

PLANT LEGEND

Symbol	Botanical Name / Common Name	Mature Size H x W	QTY	Water Requirement	Sun/Shade	Design Feature
	Coprosma repens 'Marble Queen' / Variegated Mirror Plant	5' x 6'	4	L/M	PS/S	EV
	Camellia sasanqua 'Yuletide' / "Yuletide" Autumn Camellia	3' x 10'	2	M	PS	AC
	Clivia miniata 'Aurea' / Yellow flowering Kaffir Lily	2' x 2'	4	M	S	FL
	Dianella tasmanica 'Variegata' / Variegated Flax Lily	2' x spreading	4	M	PS/S	FDN
	Woodwardia fimbriata / Giant Chain Fern	4' x 5'	3	M	PS/S	EV
	Chondropetalum Tectorum / Small Cape Rush	3' x 4'	1	M	FS/S	AC
	Ceanothus griseus horizontalis 'Yankee Point' / Ceanothus 'Yankee Point'	2.5' x 6-8'	6	L	FS/S	GC
	Salvia chiapensis / Chiapas Sage	3' x 4'	3	M	PS/S	FL/AC
	Raphiolepis indica 'Ballerina' / Dwarf Indian Hawthorne	2' x 4'	22	L/M	FS/S	GC
	Erigeron karvinskianus / Santa Barbara Daisy	1' x 4'	2	M	FS/S	GC
	Campanula portenschlagiana / Dalmation Bellflower	6" x 1.5'	25	M	PS	GC

KEY

Water Requirement

VL = Very Low
L = Low
M = Moderate

Sun/Shade


FS = Full Sun
PS = Partial Shade
S = Shade

Design Feature

AC = Accent
EV = Evergreen
FA = Fall Color
FDN = Foundation Plant
FL = Flower
FR = Fruit
GRS = Ornamental Grass
GC = Ground Cover



Coprosma repens 'Marble Queen'



Camellia sasanqua 'Yuletide'



Clivia miniata 'Aurea'




Dianella tasmanica 'Variegata'




Woodwardia fimbriata



Chondropetalum Tectorum




Ceanothus griseus horizontalis 'Yankee Point'




Salvia chiapensis



Raphiolepis indica 'Ballerina'



Erigeron karvinskianus



Campanula portenschlagiana

SUSTAINABILITY LEGEND



Dry Riverbed




Rain Barrel

***All Turf Removal Program projects must include a minimum of 3 plants per 100 square feet removed and at least one approved sustainability feature. Refer to the MWDOC Turf Removal Program's website for more information.













MEDITERRANEAN LANDSCAPE

Shade Exposure

SUBSURFACE DRIP IRRIGATION PLAN



IRRIGATION SYMBOL LEGEND

-  New or Existing Smart Irrigation Controller
-  New or Existing Rain Shutoff Device
-  Existing Water Meter
-  Existing Anti-Siphon Irrigation Control Valve w/ In-line Filter and Pressure Reducer (30 psi)
-  Existing Ball Valve to Isolate Irrigation System
-  Existing Irrigation Mainline
-  New or Existing Irrigation Lateral Line
-  New or Existing Pipe Sleeve Underneath Hardscape
-  Existing House Water Service Line
-  Zone 1 - Shade Foundation Subsurface Drip Irrigation
-  Zone 2 - Shade Landscape Subsurface Drip Irrigation
-  Zone 3 - Shade Landscape Subsurface Drip Irrigation

Smart Irrigation Controller

There are many different smart controllers on the market that are excellent for residential applications. Price points vary but features can include local weather data and adjustments, rain shut-off, Wi-Fi connectivity, access from a smart phone, and detailed water-use reporting.



Anti-Siphon Irrigation Control Valve

Above-ground, install drip filter and pressure regulator on downstream outlet side.



In-line Filter for Drip Line

Internal screen/mesh prevents clogging of drip components. Install downstream of valve.



Pressure Reducer

Pressure reduced to 30 psi for proper operation of drip system. Install downstream of filter..



Subsurface Drip Line

Emitters are built or fused into the drip tube (in-line) and spaced at different intervals such as 6, 12, and 18 inches.



Rain Sensor (Wireless)

Rain sensor with bracket installed on outdoor exposed location. Transmits to receiver near irrigation controller..